1426-1446 East Baltimore Street (Commercial Buildings)
1440 East Baltimore Street
Baltimore (Independent City)
Maryland

HABS No. MD-904-G

HABS MD, 4-BALT, 153G-

WRITTEN HISTORICAL AND DESCRIPTIVE DATA

HISTORIC AMERICAN BUTLDINGS SURVEY
MID-ATLANTIC REGION, NATIONAL PARK SERVICE
DEPARTMENT OF THE INTERIOR
PHILADELPHIA, PENNSYLVANIA 19106

Form 10-920 (June 1983)

UNITED STATES DEPARTMENT OF THE INTERIOR NATIONAL PARK SERVICE

HABS MD, 4-BALT, 153G-

ARCHITECTURAL DATA FORM

				_ <i>15</i> 3G-
STATE	COUNTY		TOWN OR VICINITY	
Mary I and			Balti	more
HISTORIC NAME OF STRUCTURE (INCL	UDE SOURCE FOR	NAME)		HABS NO.
426-46 East Baltimore Street (Commercial Buildings)			MD-904-G	
SECONDARY OR COMMON NAMES OF STRUCTURE				
1440 East Baltimore Street				
COMPLETE ADDRESS (DESCRIBE LOCATION FOR RURAL SITES)				
1440 East Baltimore Street				
DATE OF CONSTRUCTION (INCLUDE SOURCE)		ARCHITECT(S) (INCLUDE SOURCE)		
c. 1860 (1869 Sachsey Map)		Unknown		
SIGNIFICANCE (ARCHITECTURAL AND HISTORICAL, INCLUDE ORIGINAL USE OF STRUCTURE) Original use presumed to be a residence based on facade which includes a marble stoop				
and a residential grouping of windows on the first floor. Use of decorative brick string-				
er courses and interior trims and mouldings are typical of the period.				
STYLE (IF APPROPRIATE) Italianate influence				
MATERIAL OF CONSTRUCTION (INCLUDE STRUCTURAL SYSTEMS)				
Brick party walls; wood jolsts and floors; built-up roof; wood doors, windows				
E AND DIMENSIONS OF STRUCTURE (SKETCHED FLOOR PLANS ON SEPARATE PAGES ARE ACCEPTABLE)				
Overall 18' x 58' Front 18' x 30' Rear 11' x 28' (see sketch plan)				
EXTERIOR FEATURES OF NOTE				
Decorative brick string courses; Red brick common bond; metal cornice (partially missing) marble steps, marble sills. Segmental-arched windows openings with decorative brickwork.				
NTERIOR FEATURES OF NOTE (DESCRIBE FLODR PLANS, IF NDT SKETCHED) Bullseye window and door trim, board and bead wainscoting in stairs and utility rooms.				
A detail of note are the transoms above all doors between public rooms (living and dining) and between major rooms and the corridor.				
MAJOR ALTERATIONS AND ADDITIONS WITH DATES				
None evident.				
PRESENT CONDITION AND USE				
Currently vacant but, in good condition.				
OTHER INFORMATION AS APPROPRIATE				
For photographs, see HABS No. MD-904.				
Building is to be renovated for cooperative housing for artists.				
SOURCES OF INFORMATION (INCLUDING LISTING ON NATIONAL REGISTER, STATE REGISTERS, ETC.)				
1869 Sachsey Map, 1887 Bromley Map, Sanborn Maps 1902, 1911, 1927, 1932				
COMPILER, AFFILIATION		*****************************		DATE
Peter C. Doo AlA Walter Sc	hamu & Associa	ites		23 Sept, 1985

